

ENDURING RESOURCES, LLC

425 Seventeenth Street, Suite 1500

Denver, Colorado 80202

Telephone: 303-573-1222

Facsimile: 303-573-0461

August 15, 2006

State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801
Attention: Ms. Diana Whitney

RE: Request to Directionally Drill and for Exception Well Location

Southam Canyon 10-25-44-32 State Lease: ML-47065

SE-SE 32-10S-25E (Bottom Hole Location)

NE-SE 32-10S-25E (Surface Location)

Uintah County, Utah

Dear Ms. Whitney:

In order to avoid steep slopes and limit surface impact, Enduring Resources, LLC ("ERLLC") has staked the surface location of the above-referenced well outside of the 400' drilling window on the Well pad of the Southam Canyon 10-25-43-32. The BHL and produced zones will be within the 400' window of the SESE.

This well will be drilled directionally and it's surface location is only 20' from the Southam Canyon 10-25-43-32 Well.

1. ***ERLLC is the only leasehold interest owner within 460 feet of any part of the well's proposed well bore and surface location.***
 - A. *ERLLC grants itself permission for the well's exception surface and BHL locations, and*
 - B. *ERLLC grants itself permission to directional drill said well.*

In the event there are any other outstanding matters preventing this APD from being approved, please let me know at your earliest convenience, 303-350-5114 (aarlian@enduringresources.com).

Very truly yours

ENDURING RESOURCES, LLC



Alvin R. (Al) Arlian
Landman – Regulatory Specialist

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

| | | | | | |
|---|--|---|--|---|-----------------------------|
| APPLICATION FOR PERMIT TO DRILL | | | | 5. MINERAL LEASE NO: ML-47065 | 6. SURFACE: State |
| 1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> | | | | 7. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> | | | | 8. UNIT OR CA AGREEMENT NAME: | |
| 2. NAME OF OPERATOR: Enduring Resources, LLC | | | | 9. WELL NAME and NUMBER: Southam Canyon 10-25-44-32 | |
| 3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220 | | | PHONE NUMBER: (303) 350-5114 | | |
| 4. LOCATION OF WELL (FOOTAGES) 660970 X 4418582Y 39.903932 - 109.116966 AT SURFACE: 2123' FSL - 555' FEL AT PROPOSED PRODUCING ZONE: 659' FSL - 662' FEL SESE 660944 X 4418135Y 39.899910 - 109.117377 | | | | 10. FIELD AND POOL, OR WILDCAT: Undesignated | |
| 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 10S 25E | | | | 12. COUNTY: Uintah | |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 11.0 Southeast of Bonanza, UT | | | | 13. STATE: UTAH | |
| 15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 555' | | 16. NUMBER OF ACRES IN LEASE: 640 | | 17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres | |
| 18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1000' + | | 19. PROPOSED DEPTH: 4,815 | | 20. BOND DESCRIPTION: RLB0008031 | |
| 21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5820' RT-KB | | 22. APPROXIMATE DATE WORK WILL START: 10/1/2006 | | 23. ESTIMATED DURATION: 20 days | |

| 24. PROPOSED CASING AND CEMENTING PROGRAM | | | | | | | |
|---|---|-----------|-------|---------------|---|-----------|--------------|
| SIZE OF HOLE | CASING SIZE, GRADE, AND WEIGHT PER FOOT | | | SETTING DEPTH | CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT | | |
| 20" | 14" | line pipe | | 40 | 3 yards | Ready Mix | |
| 11" | 8-5/8" | J-55 | 24# | 1,716 | Premium Lead | 110 sxs | 3.50 11.1 |
| | | | | | Premium Tail | 183 sxs | 1.15 15.8 |
| 7-7/8" | 4-1/2" | N-80 | 11.6# | 4,815 | Class G | 21 sxs | 3.3 11.0 |
| | | | | | 50/50 Poz Class G | 581sxs | 1.56 14.3 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| 25. ATTACHMENTS | |
|--|--|
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES: | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Alvin R. (Al) Arlian TITLE Landman - Regulatory Specialist
 SIGNATURE *Al Arlian* DATE 7/19/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-38481

**Approved by the
Utah Division of
Oil, Gas and Mining**

APPROVAL:

Date: 12-18-06

By: *[Signature]*

(See Instructions on Reverse Side)


RECEIVED
AUG 17 2006

DIV. OF OIL, GAS & MINING

T10S, R25E, S.L.B.&M.

ENDURING RESOURCES


WELL LOCATION, TOP OF HOLE FOR THE SOUTHAM CANYON 10-25-44-32, THE TOP OF HOLE LOCATED AS SHOWN IN THE NE 1/4 SE 1/4, THE BOTTOM HOLE LOCATED AS SHOWN IN THE SE 1/4 SE 1/4 OF SECTION 32, T10S, R25E, S.L.B.&M. UTAH COUNTY, UTAH.



NOTES:

- The Bottom of hole bears S04°08'22"W 1468.37' from the Top of Hole.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (WEAVER RIDGE)

SOUTHAM CANYON 10-25-44-32
 (Surface Location) NAD 83
 LATITUDE = 39° 54' 14.47"
 LONGITUDE = 109° 07' 03.11"

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

| | | |
|-------------------------|-------------------|-----------------------------|
| DATE DRAWN: 10-27-05 | SURVEYED BY: J.H. | SHEET 2b OF 10 |
| REVISED: | DRAWN BY: F.T.M. | |
| NOTES: | SCALE: 1" = 1000' | |

**Enduring Resources, LLC
Southam Canyon 10-25-44-32
SE-SE 32-10S-25E (Bottom Hole Location)
NE-SE 32-10S-25E (Surface Location)
Uintah County, Utah
State Lease: ML-47065**

ONSHORE ORDER 1 - DRILLING PLAN

1. Estimated Tops of Geological Markers:

| Formation | Depth (K.B.) |
|-------------|--------------|
| Uinta | Surface |
| Green River | Surface |
| Wasatch | 2030 |
| Mesaverde | 2890 |

2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:

| Substance | Formation | Depth (K.B.) |
|-----------|---------------------------|--------------|
| | | |
| | KB-Uinta Elevation: 5820' | |
| Oil / Gas | Green River | Surface |
| Oil /Gas | Wasatch | 2030 |
| Oil /Gas | Mesaverde | 2890 |
| | Estimated TD | 4815 |

An 11" hole will be drilled to only approximately 1,716 feet because it is a directional well. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

3. Pressure Control Equipment: (3000 psi schematic attached)

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

4. Proposed Casing & Cementing Program:

A. Casing Program: All New

| Hole Size | Casing Size | Wt./Ft. | Grade | Joint | Depth Set (MD) |
|-----------|-------------|---------|-------|-------|----------------------|
| 20" | 14" O.D. | | | | 40' (GL) |
| 11" | 8-5/8" | 24# | J-55 | ST&C | 0 – 1,716' (KB) est. |
| 7-7/8" | 4-1/2" | 11.6# | N-80 | LT&C | 0 – 5820' (KB) |

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

B. Casing Design Parameters:

| Depth (MD) | Casing | Collapse(psi)/SF | Burst (psi)/SF | Tension(mlbs)/SF |
|------------|-----------------------------|------------------|----------------|------------------|
| 40' (GL) | 14" OD | | | |
| 1716' (KB) | 8-5/8", 24#/ft, J55, STC | 1370/1.52(a) | 2950/3.28(b) | 244/5.81(c) |
| 5820' (KB) | 4-1/2", 11.6#/ft, N-80, LTC | 6350/2.54(d) | 7780/3.38(e) | 223/4.65(f) |

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

PROPOSED CEMENTING PROGRAM

Surface Casing (if well will circulate)-Cemented to surface

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|--------|-------------|---|-----|------------|--------------|-----------------------------|
| 8-5/8" | Lead | 1216 | Premium cement + 16% gel + 0.25 pps celloflake | 110 | 25% | 11.1 | 3.50 |
| 8-5/8" | Tail | 500 | Premium cement + 2% CaCl ₂ + 0.25 pps celloflake | 138 | 25% | 15.8 | 1.15 |

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft³/sx) cement will be premium cement w/ 3% CaCl₂.+0.25 pps celloflake. Volume as required

Surface Casing (if well will not circulate) - Cemented to surface

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|---------|-------------|---|---------|------------|--------------|-----------------------------|
| 8-5/8" | Lead | 500 | Premium cement + 2% CaCl ₂ + 0.25 pps celloflake | 138 | 25 | 15.8 | 1.15 |
| 8-5/8" | Top job | As req. | Premium cement + 3% CaCl ₂ + 0.25 pps celloflake | As Req. | | 15.8 | 1.15 |

Production Casing and Liner - Cemented TD to 300' above base of surface casing

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|--------|-------------|---|-----|---------------------------------------|--------------|-----------------------------|
| 4-1/2" | Lead | 214 | Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender | 21 | 25 | 11.0 | 3.3 |
| 4-1/2" | Tail | 3185 | 50/50 POZ Class G + 2% gel + 1% CaCl ₂ + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam | 581 | 25 <i>4e forced update 8/30/06</i> | 14.3 | 1.56 |

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. **Drilling Fluids (mud) Program:**

| Interval (MD) | Mud Weight | Fluid Loss | Viscosity | Mud Type |
|-------------------|------------|------------|-----------|-----------|
| 0' - 1716' (KB) | | No cntrl | | Air/mist |
| 1,716'-3000' (KB) | 8.4-8.6 | No cntrl | 28-36 | Water |
| 3000'-5820' (KB) | 8.8-9.8 | 8 - 10 ml | 32-42 | Water/Gel |

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. **Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. **Abnormal Conditions:**

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 2,504 psi (calculated at 0.52psi/foot of hole) and maximum anticipated surface pressure equals approximately 1,445 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. **Anticipated Starting Dates:**

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. **Variances:**

None anticipated

10. **Other:**

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Single Shot directional surveys will be dropped every 2000 feet to monitor hole angle.

**Directions to the Well Pad for:
Southam Canyon 10-25-43-32
Southam Canyon 10-25-44-32**

Pad Location: NESE of Sec. 32, T10S, R25E, S.L.B.&M.

Beginning at the city of Bonanza, Utah. Leave the city of Bonanza heading south on U.S. Highway 45, which becomes a paved road, for a distance of approximately 3.7 miles where the road turns left at a gaging station. Do not turn left. Continue southeasterly on the same road for a distance of 5.9 miles, where there is a fork in the road. Turn left, and proceed for a distance of approximately 1.2 miles. Turn right and bear westerly approximately 0.2 miles to the beginning of the proposed access. Thence proceed southerly for approximately 3,430 feet (0.6 miles) along the proposed access to the proposed well pad.

Enduring Resources, LLC

Southam Canyon 10-25-44-32

SE-SE 32-10S-25E (Bottom Hole Location)

NE-SE 32-10S-25E (Surface Location)

Uintah County, Utah

State Lease: ML-47065

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. Existing Roads:

Directions to the Southam Canyon 10-25-44-32 Well Pad.

Beginning at the city of Bonanza, Utah. Leave the city of Bonanza heading south on U.S. highway 45, which becomes a paved road, for a distance of approximately 3.7 miles where the road turns left at a gaging station. Do not turn left. Continue southeasterly on the same road for a distance of 5.9 miles, where there is a fork in the road. Turn left, and proceed for a distance of approximately 1.2 miles. Turn right and bear westerly approximately 0.2 miles to the beginning of the proposed access. Thence proceed southerly for approximately 3,430 feet (0.6 miles) along the proposed access to the proposed well pad.

2. Planned Access Roads:

The proposed access road will be approximately 3,140 feet of new construction all on-lease. Off-lease access will be 290 feet of construction. There is a Right Of Way pending with the BLM.

ALL NEW CONSTRUCTION IS ON SITLA AND BLM LANDS.

The proposed access road will be utilized to transport personnel, equipment and supplies to and from the proposed well site during drilling, completion and production operations. The road will be utilized year round.

The access road will be crowned 2% to 3%, ditched and constructed with a running surface of 18 feet and a maximum disturbed width of 30 feet right-of-way. Maximum grade of road is 5% or less. Graveling or capping the roadbed will be performed as necessary to provide a well constructed, safe road. No fence crossings, culverts, turnouts, cattle guards or major cuts and fills are required. Prior to construction or upgrading, the proposed road shall be cleared of any snow and allowed to dry completely.

Surface disturbance and vehicular traffic will be limited to the proposed location and proposed access route. Any additional area needed will be approved in advance. All construction shall be in conformance with the standards outlined in the BLM and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development. 1989.

The road surface and shoulders will be kept in a safe usable condition and will be maintained in accordance with the original construction standards. All drainage ditches will be kept clear and free flowing and will be maintained according to original

construction standards. The access road surface will be kept free of trash during operations. All traffic will be confined to the approved disturbed surface. Road drainage crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossing nor shall the drainages be blocked by the road bed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided. When snow is removed from the road during the winter months, the snow shall be pushed outside of the borrow ditches and the turnouts kept clear so that snowmelt will be channeled away from the road.

3. **Location of Existing Wells within a One-Mile radius (See "Topo" Map "C" attached):**

The following wells are wells located within a one (1) mile or greater radius of the proposed location.

- | | | |
|----|-------|---|
| a. | None: | Water Wells: |
| b. | None: | Injection Wells: |
| c. | None: | Producing Wells: |
| d. | None: | Drilling Wells: |
| e. | None: | Shut-in Wells: |
| f. | None: | Temporarily Abandoned Wells: |
| g. | None: | Disposal Wells: |
| h. | None: | Abandoned Wells: |
| i. | None: | Dry Holes: |
| j. | None: | Observation Wells: |
| k. | (10): | Pending (staked) Wells: |
| | | i. Enduring has ten other wells staked in this section. |

4. **Location of Existing and/or Proposed Facilities:**

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e. production tanks, produced water tanks and/or heater treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank and be independent of the back cut.

All permanent (on site for six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Inter-Agency Committee

All facilities will be painted within 6 months of installation. The color shall be designated by DOG&M and SITLA. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

Gas Gathering Pipeline for this well will be:

| | | | |
|--------|------------------|-----------|-------|
| 6,455' | Surface Pipeline | On-Lease | SITLA |
| -0- | Surface Pipeline | Off-Lease | n/a |

If this well is capable of economic production, a 4" (or less) steel surface gas gathering line and related equipment shall be installed. The surface gas gathering line shall be in use year round. A total of approximately less than 6,455 feet of surface gas gathering pipeline shall be laid on the surface to minimize surface disturbance:

The proposed pipeline will begin at the well site; and be laid on the surface next to the new access road to tie-in to a steel surface pipeline that is located next to the county road.

The meter run will be housed. The gas gathering line will be buried or anchored down from the wellhead to the meter.

Upon plugging and abandonment, the gas gathering line will be removed and the disturbed area will be re-contoured and restored as near as practical to the original condition. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

5. Location and Type of Water Supply:

Water will be purchased from American Gilsonite from the following source. Water Right No. 49-222, Application/Claim No. A29909/a4958, Certificate No. 9915 ("AGC Water Right"). The AGC Water Right consists of nineteen underground water wells located in Sec.2, T10S, R24E, SLBM, piped to and stored in a cistern located in Section 25, T9S, R24E.

Water will be hauled to the location over the roads marked on "Topo" Maps "A" and "B."

No water well is to be drilled on this lease.

6. Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized for location and access road construction.

Any gravel will be obtained from a commercial source; however, gravel sized rock debris associated with location and access road construction may be used as access road surfacing material.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, brake or allow discharge of liquids.

The reserve pit will be lined with ¼ felt and a minimum of 16 mm plastic with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the will be disposed of in the pit.

A chemical portable toilet will be furnished with the drilling rig. The toilet will be replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

Garbage, trash and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash well is burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported or disposed of in association with the drilling, completion or testing of this well.

Produced oil will be stored in an oil tank and then hauled by truck to a crude purchaser facility. Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to an approved disposal site.

8. Ancillary Facilities:

During drilling operations, approximately 20 days, the site will be a manned camp. Three or four additional trailers will be on location to serve as the crews' housing and eating facilities. These will be located on the perimeter of the pad site within the topsoil

stockpiles. Refer to Sheet 4.

9. Well Site Layout: (Refer to Sheets #2, #3, and #4)

The attached Location Layout Diagrams described drill pad cross-sections, cuts and fills and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s) and surface material stockpiles(s).

Please see the attached diagram for rig orientation and access roads.

The top soil will be windrowed rather than piled. It will be reseeded and track walker at the time the location is constructed. Seeding will be with the determined during the onsite. (Refer to "Seed Mixture for Windrowed Top Soil Will included:" following herein.

The top soil removed from the pit area will be store separately and will not be reseeded until the pit is reclaimed.

All pits shall be fence to the following minimum standards:

- a. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- b. The net wire shall be no more than 2 inches above the ground. The barbed wire shall be 3 inches over the new wire. Total height of the fence shall be at least 42 inches.
- c. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- d. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two fence posts shall be no greater than 16 feet.
- e. All wire shall be stretched by, using a stretching device, before it is attached to corner posts.
- f. The reserve pit fencing will be on three sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.
- g. Location size may change prior to drilling the well due to the current rig availability. If the proposed location is not large enough to accommodate the drilling, the location will be re-surveyed and a Form 9 will be submitted.

10. Plans for Surface Reclamation:

Producing Location:

- a. Immediately upon well completion the location and surrounding area will be cleared of all unused tubing, equipment, materials, trash and debris not required for production.
- b. Immediately upon well completion any hydrocarbons in the pit shall be removed in accordance with 40CFR 3162.7.

- c. Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.
- d. The reserve pit **and** that portion of the location not needed for production facilities/operations will be re-contoured to the approximated natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.
- e. To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface 3 feet above surrounding round surface to allow the reclaimed pit area to drain effectively.
- f. Upon completion of back filling, leveling and re-contouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

- i. Abandoned well sites, roads and other disturbed areas will be restored as nearly as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions and re-establishment of vegetation as specified.
- ii. All disturbed surfaces will be re-contoured to the approximated natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. If necessary, re-seeding operations will be performed after completion of other reclamation operations.

Seed Mixture for Windrowed Top Soil Will Included:

To be provided by the DOG&M and/or SITLA.

11. Surface Ownership: Location, Access and Pipeline Route:

Wellsite: SITLA

Access: SITLA, BLM

Pipeline: SITLA

12. Other Information**On-site Inspection for Location, Access and Pipeline Route:**

The on-site will be scheduled by SITLA and DOG&M.

Special Conditions of Approval:

- Tanks and Production Equipment shall be painted Dark Olive Black.
- Surface Gathering Pipeline shall be 4" or less

Archeology:

- a. A Cultural Resource Inventory Report is pending and to be prepared by Montgomery Archaeological Consultants.

Paleontology:

- a. A Paleontology Reconnaissance Report is pending and to be prepared by Intermountain Paleo-Consulting.

If, during operations, any archaeological or historical sites, or any objects of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites will be suspended and the discovery reported promptly to the surface management agency.


13, Lessee's or Operator's Representatives:**Representatives:**

Alvin R. (Al) Arlian
Landman – Regulatory Specialist
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-350-5114
Fax Tel: 303-573-0461
aarlian@enduringresources.com


Teme Singleton
Drilling Engineer
Enduring Resources, LLC
475 17th Street, Suite 1500
Denver, Colorado 80202
Office Tel: 303-573-5711
Fax Tel: 303-573-0461
tsingleton@enduringresources.com

ENDURING RESOURCES, LLC

TYPICAL 3,000 p.s.i. BLOWOUT PREVENTER SCHEMATIC



TYPICAL 3,000 p.s.i. CHOKE MANIFOLD SCHEMATIC





ENDURING RESOURCES
Southam Canyon 10-25-44-32
NE/SE Sec. 32, T10S, R25E
Uintah County, Utah



SECTION DETAILS

| Sec | MD | Inc | Azi | TVD | +N/-S | +E/-W | DLeg | TFace | VSec | Target |
|-----|---------|-------|--------|---------|----------|---------|------|--------|---------|------------|
| 1 | 0.00 | 0.00 | 184.14 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 2 | 400.00 | 0.00 | 184.14 | 400.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | KOP |
| 3 | 1168.24 | 38.41 | 184.14 | 1111.97 | -247.37 | -17.91 | 5.00 | 184.14 | 248.02 | End Build |
| 4 | 2633.43 | 38.41 | 184.14 | 2260.04 | -1155.33 | -83.63 | 0.00 | 0.00 | 1158.35 | Start Drop |
| 5 | 3593.72 | 0.00 | 184.14 | 3150.00 | -1464.54 | -106.01 | 4.00 | 180.00 | 1468.37 | End Drop |
| 6 | 5258.72 | 0.00 | 184.14 | 4815.00 | -1464.54 | -106.01 | 0.00 | 184.14 | 1468.37 | TD |

WELL DETAILS

| Name | +N/-S | +E/-W | Northing | Easting | Latitude | Longitude | Slot |
|----------------------------|-------|-------|------------|------------|---------------|----------------|------|
| Southam Canyon 10-25-44-32 | 0.00 | 0.00 | 7142677.99 | 2308688.52 | 39°54'14.470N | 109°07'03.110W | N/A |

FIELD DETAILS

Uintah, Utah
Utah Central Zone
U.S.A.

Geodetic System: US State Plane Coordinate System 1983
Ellipsoid: GRS 1980
Zone: Utah, Central Zone
Magnetic Model: igrf2005

System Datum: Mean Sea Level
Local North: True North

SITE DETAILS

NE/SE 32-10S-25E
Sec. 32, T10S, R25E, Uintah County, Utah
2123 FSL & 555 FEL



Site Centre Latitude: 39°54'14.470N
Longitude: 109°07'03.110W
Ground Level: 5803.70
Positional Uncertainty: 0.00
Convergence: 1.53

TARGET DETAILS

| Name | TVD | +N/-S | +E/-W | Shape |
|--------------------|---------|----------|---------|---------------------|
| 10-25-44-32 Target | 4815.00 | -1464.54 | -106.01 | Rectangle (400x400) |

FORMATION TOP DETAILS

| No. | TVDPath | MDPath | Formation |
|-----|---------|---------|-------------|
| 1 | 0.00 | 0.00 | Green River |
| 2 | 2030.00 | 2339.84 | Wasatch |
| 3 | 2890.00 | 3332.27 | Mesaverde |
| 4 | 4575.00 | 5018.72 | Buck Tongue |



Weatherford International

Planning Report

| | |
|--|---|
| Company: Enduring Resources Field: Uintah, Utah Site: NE/SE 32-10S-25E Well: Southam Canyon 10-25-44-32 Wellpath: 1 | Date: 7/12/2006 Co-ordinate(NE) Reference: Well: Southam Canyon 10-25-44-32 Vertical (TVD) Reference: SITE 5820.0 Section (VS) Reference: Well (0.00N,0.00E,184.14Azi) Plan: Plan #1 |
|--|---|

| | |
|---|--|
| Field: Uintah, Utah Utah Central Zone U.S.A. Map System: US State Plane Coordinate System 1983 Geo Datum: GRS 1980 Sys Datum: Mean Sea Level | Map Zone: Utah, Central Zone Coordinate System: Well Centre Geomagnetic Model: igrf2005 |
|---|--|

| | |
|--|--|
| Site: NE/SE 32-10S-25E Sec. 32, T10S, R25E, Uintah County, Utah 2123 FSL & 555 FEL Site Position: From: Geographic Position Uncertainty: 0.00 ft Ground Level: 5803.70 ft | Northing: 7142677.99 ft Easting: 2308688.52 ft Latitude: 39 54 14.470 N Longitude: 109 7 3.110 W North Reference: True Grid Convergence: 1.53 deg |
|--|--|

| | |
|---|--|
| Well: Southam Canyon 10-25-44-32 Well Position: +N/-S 0.00 ft +E/-W 0.00 ft Position Uncertainty: 0.00 ft | Slot Name: Northing: 7142677.99 ft Easting: 2308688.52 ft Latitude: 39 54 14.470 N Longitude: 109 7 3.110 W |
|---|--|

| | |
|---|--|
| Wellpath: 1 Current Datum: SITE Magnetic Data: 7/11/2006 Field Strength: 52879 nT Vertical Section: Depth From (TVD) ft | Height 5820.00 ft Drilled From: Surface Tie-on Depth: 0.00 ft Above System Datum: Mean Sea Level Declination: 11.52 deg Mag Dip Angle: 66.00 deg +N/-S ft +E/-W ft Direction deg 0.00 0.00 0.00 184.14 |
|---|--|

| | |
|---|--|
| Plan: Plan #1 Principal: Yes | Date Composed: 7/12/2006 Version: 1 Tied-to: From Surface |
|---|--|

Plan Section Information

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg | Target |
|----------|-------------|-------------|-----------|-------------|-------------|------------------|--------------------|-------------------|------------|--------------------|
| 0.00 | 0.00 | 184.14 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 400.00 | 0.00 | 184.14 | 400.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1168.24 | 38.41 | 184.14 | 1111.97 | -247.37 | -17.91 | 5.00 | 5.00 | 0.00 | 184.14 | |
| 2633.43 | 38.41 | 184.14 | 2260.04 | -1155.33 | -83.63 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 3593.72 | 0.00 | 184.14 | 3150.00 | -1464.54 | -106.01 | 4.00 | -4.00 | 0.00 | 180.00 | |
| 5258.72 | 0.00 | 184.14 | 4815.00 | -1464.54 | -106.01 | 0.00 | 0.00 | 0.00 | 184.14 | 10-25-44-32 Target |

Section 1 : Start Hold

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|------------|
| 0.00 | 0.00 | 184.14 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 400.00 | 0.00 | 184.14 | 400.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 184.14 |

Section 2 : Start Build 5.00

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|------------|
| 500.00 | 5.00 | 184.14 | 499.87 | -4.35 | -0.31 | 4.36 | 5.00 | 5.00 | 0.00 | 0.00 |
| 600.00 | 10.00 | 184.14 | 598.99 | -17.36 | -1.26 | 17.41 | 5.00 | 5.00 | 0.00 | 0.00 |
| 700.00 | 15.00 | 184.14 | 696.58 | -38.94 | -2.82 | 39.05 | 5.00 | 5.00 | 0.00 | 0.00 |
| 800.00 | 20.00 | 184.14 | 791.93 | -68.93 | -4.99 | 69.11 | 5.00 | 5.00 | 0.00 | 0.00 |
| 900.00 | 25.00 | 184.14 | 884.28 | -107.08 | -7.75 | 107.36 | 5.00 | 5.00 | 0.00 | 0.00 |
| 1000.00 | 30.00 | 184.14 | 972.96 | -153.12 | -11.08 | 153.52 | 5.00 | 5.00 | 0.00 | 0.00 |
| 1100.00 | 35.00 | 184.14 | 1057.27 | -206.70 | -14.96 | 207.24 | 5.00 | 5.00 | 0.00 | 0.00 |
| 1168.24 | 38.41 | 184.14 | 1111.97 | -247.37 | -17.91 | 248.02 | 5.00 | 5.00 | 0.00 | 0.00 |

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SE 32-10S-25E
Well: Southam Canyon 10-25-44-32
Wellpath: 1

Date: 7/12/2006 **Time:** 09:12:21 **Page:** 2
Co-ordinate(NE) Reference: Well: Southam Canyon 10-25-44-32
Vertical (TVD) Reference: SITE 5820.0
Section (VS) Reference: Well (0.00N,0.00E,184.14Azi)
Plan: Plan #1

Section 3 : Start Hold

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|------------|
| 1200.00 | 38.41 | 184.14 | 1136.86 | -267.05 | -19.33 | 267.75 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1300.00 | 38.41 | 184.14 | 1215.21 | -329.02 | -23.82 | 329.88 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1400.00 | 38.41 | 184.14 | 1293.57 | -390.99 | -28.30 | 392.01 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1500.00 | 38.41 | 184.14 | 1371.93 | -452.96 | -32.79 | 454.14 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1600.00 | 38.41 | 184.14 | 1450.28 | -514.93 | -37.27 | 516.27 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1700.00 | 38.41 | 184.14 | 1528.64 | -576.90 | -41.76 | 578.41 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1800.00 | 38.41 | 184.14 | 1607.00 | -638.86 | -46.24 | 640.54 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1900.00 | 38.41 | 184.14 | 1685.35 | -700.83 | -50.73 | 702.67 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2000.00 | 38.41 | 184.14 | 1763.71 | -762.80 | -55.21 | 764.80 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2100.00 | 38.41 | 184.14 | 1842.07 | -824.77 | -59.70 | 826.93 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2200.00 | 38.41 | 184.14 | 1920.42 | -886.74 | -64.18 | 889.06 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2300.00 | 38.41 | 184.14 | 1998.78 | -948.71 | -68.67 | 951.19 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2339.84 | 38.41 | 184.14 | 2030.00 | -973.40 | -70.46 | 975.95 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2400.00 | 38.41 | 184.14 | 2077.14 | -1010.68 | -73.16 | 1013.32 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2500.00 | 38.41 | 184.14 | 2155.49 | -1072.65 | -77.64 | 1075.45 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2600.00 | 38.41 | 184.14 | 2233.85 | -1134.61 | -82.13 | 1137.58 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2633.43 | 38.41 | 184.14 | 2260.04 | -1155.33 | -83.63 | 1158.35 | 0.00 | 0.00 | 0.00 | 0.00 |

Section 4 : Start Drop -4.00

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|------------|
| 2700.00 | 35.75 | 184.14 | 2313.15 | -1195.36 | -86.52 | 1198.49 | 4.00 | -4.00 | 0.00 | -180.00 |
| 2800.00 | 31.75 | 184.14 | 2396.28 | -1250.76 | -90.53 | 1254.03 | 4.00 | -4.00 | 0.00 | 180.00 |
| 2900.00 | 27.75 | 184.14 | 2483.08 | -1300.24 | -94.11 | 1303.64 | 4.00 | -4.00 | 0.00 | 180.00 |
| 2952.52 | 25.65 | 184.14 | 2530.00 | -1323.77 | -95.82 | 1327.24 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3000.00 | 23.75 | 184.14 | 2573.14 | -1343.56 | -97.25 | 1347.07 | 4.00 | -4.00 | 0.00 | -180.00 |
| 3100.00 | 19.75 | 184.14 | 2666.00 | -1380.51 | -99.92 | 1384.12 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3200.00 | 15.75 | 184.14 | 2761.22 | -1410.91 | -102.13 | 1414.60 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3300.00 | 11.75 | 184.14 | 2858.33 | -1434.61 | -103.84 | 1438.36 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3332.27 | 10.46 | 184.14 | 2890.00 | -1440.81 | -104.29 | 1444.58 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3400.00 | 7.75 | 184.14 | 2956.87 | -1451.49 | -105.06 | 1455.29 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3500.00 | 3.75 | 184.14 | 3056.35 | -1461.48 | -105.79 | 1465.31 | 4.00 | -4.00 | 0.00 | 180.00 |
| 3593.72 | 0.00 | 184.14 | 3150.00 | -1464.54 | -106.01 | 1468.37 | 4.00 | -4.00 | 0.00 | -180.00 |

Section 5 : Start Hold

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | TFO deg |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|------------|
| 3600.00 | 0.00 | 184.14 | 3156.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 3700.00 | 0.00 | 184.14 | 3256.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 3800.00 | 0.00 | 184.14 | 3356.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 3900.00 | 0.00 | 184.14 | 3456.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4000.00 | 0.00 | 184.14 | 3556.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4100.00 | 0.00 | 184.14 | 3656.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4200.00 | 0.00 | 184.14 | 3756.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4300.00 | 0.00 | 184.14 | 3856.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4400.00 | 0.00 | 184.14 | 3956.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4500.00 | 0.00 | 184.14 | 4056.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4600.00 | 0.00 | 184.14 | 4156.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4700.00 | 0.00 | 184.14 | 4256.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4800.00 | 0.00 | 184.14 | 4356.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 4900.00 | 0.00 | 184.14 | 4456.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 5000.00 | 0.00 | 184.14 | 4556.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 5018.72 | 0.00 | 184.14 | 4575.00 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 5100.00 | 0.00 | 184.14 | 4656.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 5200.00 | 0.00 | 184.14 | 4756.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |
| 5258.72 | 0.00 | 184.14 | 4815.00 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 184.14 |

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SE 32-10S-25E
Well: Southam Canyon 10-25-44-32
Wellpath: 1

Date: 7/12/2006 **Time:** 09:12:21 **Page:** 3
Co-ordinate(NE) Reference: Well: Southam Canyon 10-25-44-32
Vertical (TVD) Reference: SITE 5820.0
Section (VS) Reference: Well (0.00N,0.00E,184.14Azi)
Plan: Plan #1

Survey

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | Tool/Comment |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|--------------|
| 400.00 | 0.00 | 184.14 | 400.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | KOP |
| 500.00 | 5.00 | 184.14 | 499.87 | -4.35 | -0.31 | 4.36 | 5.00 | 5.00 | 0.00 | MWD |
| 600.00 | 10.00 | 184.14 | 598.99 | -17.36 | -1.26 | 17.41 | 5.00 | 5.00 | 0.00 | MWD |
| 700.00 | 15.00 | 184.14 | 696.58 | -38.94 | -2.82 | 39.05 | 5.00 | 5.00 | 0.00 | MWD |
| 800.00 | 20.00 | 184.14 | 791.93 | -68.93 | -4.99 | 69.11 | 5.00 | 5.00 | 0.00 | MWD |
| 900.00 | 25.00 | 184.14 | 884.28 | -107.08 | -7.75 | 107.36 | 5.00 | 5.00 | 0.00 | MWD |
| 1000.00 | 30.00 | 184.14 | 972.96 | -153.12 | -11.08 | 153.52 | 5.00 | 5.00 | 0.00 | MWD |
| 1100.00 | 35.00 | 184.14 | 1057.27 | -206.70 | -14.96 | 207.24 | 5.00 | 5.00 | 0.00 | MWD |
| 1168.24 | 38.41 | 184.14 | 1111.97 | -247.37 | -17.91 | 248.02 | 5.00 | 5.00 | 0.00 | End Build |
| 1200.00 | 38.41 | 184.14 | 1136.86 | -267.05 | -19.33 | 267.75 | 0.00 | 0.00 | 0.00 | MWD |
| 1300.00 | 38.41 | 184.14 | 1215.21 | -329.02 | -23.82 | 329.88 | 0.00 | 0.00 | 0.00 | MWD |
| 1400.00 | 38.41 | 184.14 | 1293.57 | -390.99 | -28.30 | 392.01 | 0.00 | 0.00 | 0.00 | MWD |
| 1500.00 | 38.41 | 184.14 | 1371.93 | -452.96 | -32.79 | 454.14 | 0.00 | 0.00 | 0.00 | MWD |
| 1600.00 | 38.41 | 184.14 | 1450.28 | -514.93 | -37.27 | 516.27 | 0.00 | 0.00 | 0.00 | MWD |
| 1700.00 | 38.41 | 184.14 | 1528.64 | -576.90 | -41.76 | 578.41 | 0.00 | 0.00 | 0.00 | MWD |
| 1800.00 | 38.41 | 184.14 | 1607.00 | -638.86 | -46.24 | 640.54 | 0.00 | 0.00 | 0.00 | MWD |
| 1900.00 | 38.41 | 184.14 | 1685.35 | -700.83 | -50.73 | 702.67 | 0.00 | 0.00 | 0.00 | MWD |
| 2000.00 | 38.41 | 184.14 | 1763.71 | -762.80 | -55.21 | 764.80 | 0.00 | 0.00 | 0.00 | MWD |
| 2100.00 | 38.41 | 184.14 | 1842.07 | -824.77 | -59.70 | 826.93 | 0.00 | 0.00 | 0.00 | MWD |
| 2200.00 | 38.41 | 184.14 | 1920.42 | -886.74 | -64.18 | 889.06 | 0.00 | 0.00 | 0.00 | MWD |
| 2300.00 | 38.41 | 184.14 | 1998.78 | -948.71 | -68.67 | 951.19 | 0.00 | 0.00 | 0.00 | MWD |
| 2339.84 | 38.41 | 184.14 | 2030.00 | -973.40 | -70.46 | 975.95 | 0.00 | 0.00 | 0.00 | Wasatch |
| 2400.00 | 38.41 | 184.14 | 2077.14 | -1010.68 | -73.16 | 1013.32 | 0.00 | 0.00 | 0.00 | MWD |
| 2500.00 | 38.41 | 184.14 | 2155.49 | -1072.65 | -77.64 | 1075.45 | 0.00 | 0.00 | 0.00 | MWD |
| 2600.00 | 38.41 | 184.14 | 2233.85 | -1134.61 | -82.13 | 1137.58 | 0.00 | 0.00 | 0.00 | MWD |
| 2633.43 | 38.41 | 184.14 | 2260.04 | -1155.33 | -83.63 | 1158.35 | 0.00 | 0.00 | 0.00 | Start Drop |
| 2700.00 | 35.75 | 184.14 | 2313.15 | -1195.36 | -86.52 | 1198.49 | 4.00 | -4.00 | 0.00 | MWD |
| 2800.00 | 31.75 | 184.14 | 2396.28 | -1250.76 | -90.53 | 1254.03 | 4.00 | -4.00 | 0.00 | MWD |
| 2900.00 | 27.75 | 184.14 | 2483.08 | -1300.24 | -94.11 | 1303.64 | 4.00 | -4.00 | 0.00 | MWD |
| 2952.52 | 25.65 | 184.14 | 2530.00 | -1323.77 | -95.82 | 1327.24 | 4.00 | -4.00 | 0.00 | Entry Point |
| 3000.00 | 23.75 | 184.14 | 2573.14 | -1343.56 | -97.25 | 1347.07 | 4.00 | -4.00 | 0.00 | MWD |
| 3100.00 | 19.75 | 184.14 | 2666.00 | -1380.51 | -99.92 | 1384.12 | 4.00 | -4.00 | 0.00 | MWD |
| 3200.00 | 15.75 | 184.14 | 2761.22 | -1410.91 | -102.13 | 1414.60 | 4.00 | -4.00 | 0.00 | MWD |
| 3300.00 | 11.75 | 184.14 | 2858.33 | -1434.61 | -103.84 | 1438.36 | 4.00 | -4.00 | 0.00 | MWD |
| 3332.27 | 10.46 | 184.14 | 2890.00 | -1440.81 | -104.29 | 1444.58 | 4.00 | -4.00 | 0.00 | Mesaverde |
| 3400.00 | 7.75 | 184.14 | 2956.87 | -1451.49 | -105.06 | 1455.29 | 4.00 | -4.00 | 0.00 | MWD |
| 3500.00 | 3.75 | 184.14 | 3056.35 | -1461.48 | -105.79 | 1465.31 | 4.00 | -4.00 | 0.00 | MWD |
| 3593.72 | 0.00 | 184.14 | 3150.00 | -1464.54 | -106.01 | 1468.37 | 4.00 | -4.00 | 0.00 | End Drop |
| 3600.00 | 0.00 | 184.14 | 3156.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 3700.00 | 0.00 | 184.14 | 3256.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 3800.00 | 0.00 | 184.14 | 3356.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 3900.00 | 0.00 | 184.14 | 3456.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4000.00 | 0.00 | 184.14 | 3556.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4100.00 | 0.00 | 184.14 | 3656.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4200.00 | 0.00 | 184.14 | 3756.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4300.00 | 0.00 | 184.14 | 3856.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4400.00 | 0.00 | 184.14 | 3956.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4500.00 | 0.00 | 184.14 | 4056.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4600.00 | 0.00 | 184.14 | 4156.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4700.00 | 0.00 | 184.14 | 4256.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4800.00 | 0.00 | 184.14 | 4356.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 4900.00 | 0.00 | 184.14 | 4456.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 5000.00 | 0.00 | 184.14 | 4556.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 5018.72 | 0.00 | 184.14 | 4575.00 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | Buck Tongue |

Weatherford International

Planning Report

Company: Enduring Resources
Field: Uintah, Utah
Site: NE/SE 32-10S-25E
Well: Southam Canyon 10-25-44-32
Wellpath: 1

Date: 7/12/2006 **Time:** 09:12:21 **Page:** 4
Co-ordinate(NE) Reference: Well: Southam Canyon 10-25-44-32
Vertical (TVD) Reference: SITE 5820.0
Section (VS) Reference: Well (0.00N,0.00E,184.14Azi)
Plan: Plan #1

Survey

| MD ft | Incl deg | Azim deg | TVD ft | +N/-S ft | +E/-W ft | VS ft | DLS deg/100ft | Build deg/100ft | Turn deg/100ft | Tool/Comment |
|----------|-------------|-------------|-----------|-------------|-------------|----------|------------------|--------------------|-------------------|--------------------|
| 5100.00 | 0.00 | 184.14 | 4656.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 5200.00 | 0.00 | 184.14 | 4756.28 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | MWD |
| 5258.72 | 0.00 | 184.14 | 4815.00 | -1464.54 | -106.01 | 1468.37 | 0.00 | 0.00 | 0.00 | 10-25-44-32 Target |

Targets

| Name | Description Dip. | Dir. | TVD ft | +N/-S ft | +E/-W ft | Map Northing ft | Map Easting ft | ← Latitude → Deg Min Sec | | | ← Longitude → Deg Min Sec | | |
|----------------------|---------------------|------|-----------|-------------|-------------|-----------------------|----------------------|-----------------------------|----|----------|------------------------------|---|---------|
| 10-25-44-32 Target | | | 4815.00 | -1464.54 | -106.01 | 7141211.15 | 2308621.56 | 39 | 53 | 59.995 N | 109 | 7 | 4.470 W |
| -Rectangle (400x400) | | | | | | | | | | | | | |
| -Plan hit target | | | | | | | | | | | | | |

Formations

| MD ft | TVD ft | Formations | Lithology | Dip Angle deg | Dip Direction deg |
|----------|-----------|-------------|-----------|------------------|----------------------|
| | 0.00 | Green River | | 0.00 | 0.00 |
| 2339.84 | 2030.00 | Wasatch | | 0.00 | 0.00 |
| 3332.27 | 2890.00 | Mesaverde | | 0.00 | 0.00 |
| 5018.72 | 4575.00 | Buck Tongue | | 0.00 | 0.00 |


Annotation

| MD ft | TVD ft | |
|----------|-----------|--------------------------|
| 400.00 | 400.00 | SHL (2123 FSL & 555 FEL) |
| 1168.24 | 1111.97 | KOP |
| 2633.43 | 2260.04 | End Build |
| 2952.52 | 2530.00 | Start Drop |
| 3593.72 | 3150.00 | Entry Point |
| 5258.72 | 4815.00 | End Drop |
| | | TD |

T10S, R25E, S.L.B.&M

ENDURING RESOURCES

SECTION DRILLING MAP
SOUTHAM CANYON 10-25-43-32
SOUTHAM CANYON 10-25-44-32



LEGEND

- = Vertical Well
- ⊙ = Directional Well / Bottom Hole


TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

| | | |
|-------------------------|-------------------|---------------------|
| DATE DRAWN: 10-27-05 | SURVEYED BY: J.H. | SHEET 1 OF 10 |
| REVISED: | DRAWN BY: F.T.M. | |
| NOTES: | SCALE: 1" = 1000' | |

ENDURING RESOURCES

WELL PAD INTERFERENCE PLAT
 SOUTHAM CANYON 10-25-43-32
 SOUTHAM CANYON 10-25-44-32
 Section 32, T10S, R25E, S.L.B.&M.



TOP HOLE FOOTAGES

10-25-43-32
 2143' FSL & 555' FEL

10-25-44-32
 2123' FSL & 555' FEL

BOTTOM HOLE FOOTAGES

10-25-43-32
 VERTICAL

10-25-44-32
 659' FSL & 662' FEL

Note:

Bearings are derived
 using true North.

RELATIVE COORDINATES From top hole to bottom hole

| WELL | NORTH | EAST |
|-------|---------|------|
| 43-32 | N/A | N/A |
| 44-32 | -1,465' | -106 |

LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

| WELL | LATITUDE | LONGITUDE |
|-------|----------------|-----------------|
| 43-32 | 39° 54' 14.66" | 109° 07' 03.11" |
| 44-32 | 39° 54' 14.47" | 109° 07' 03.11" |

SURVEYED BY: J.H. DATE DRAWN: 10-27-05

DRAWN BY: F.T.M. SCALE: 1" = 60'

NOTES:

Tri State
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

(435) 781-2501


SHEET
 3
 OF 10

ENDURING RESOURCES

SOUTHAM CANYON 10-25-43-32

SOUTHAM CANYON 10-25-44-32

Section 32, T10S, R25E, S.L.B.&M.



SURVEYED BY: J.H. DATE DRAWN: 10-27-05
 DRAWN BY: F.T.M. SCALE: 1" = 60'
 NOTES:

Tri State
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078
 (435) 781-2501





SHEET
 4
 OF 10

ENDURING RESOURCES

CROSS SECTIONS

SOUTHAM CANYON 10-25-43-32

SOUTHAM CANYON 10-25-44-32



NOTE:
UNLESS OTHERWISE NOTED
CUT SLOPES ARE AT 1:1
FILL SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)

| ITEM | CUT | FILL | 6" TOPSOIL | EXCESS |
|--------|--------|-------|--|--------|
| PAD | 11,360 | 7,100 | Topsoil is not included in Pad Cut | 4,260 |
| PIT | 5,390 | 0 | | 5,390 |
| TOTALS | 16,750 | 7,100 | 1,880 | 9,650 |

SURVEYED BY: J.H. DATE DRAWN: 10-27-05

DRAWN BY: F.T.M. SCALE: 1" = 60'

NOTES:

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078


SHEET
5
OF 10

ENDURING RESOURCES

TYPICAL RIG LAYOUT

SOUTHAM CANYON 10-25-43-32

SOUTHAM CANYON 10-25-44-32




FLARE
PIT

Note:
Flare pit is to be
located at least
100' from well head.

| | |
|-------------------|----------------------|
| SURVEYED BY: J.H. | DATE DRAWN: 10-27-05 |
| DRAWN BY: F.T.M. | SCALE: 1" = 60' |
| NOTES: | |

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501

SHEET
6
OF 10



ENDURING RESOURCES

Southam Canyon 10-25-43-32

Southam Canyon 10-25-44-32

Pad Location: NESE of Sec. 32, T10S, R25E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000

DRAWN BY: bgm

DATE: 07-17-2006

Legend

- Existing Road
- Proposed Access


TOPOGRAPHIC MAP

"A"

SHEET

7

OF 10



ENDURING RESOURCES

Southam Canyon 10-25-43-32

Southam Canyon 10-25-44-32

Pad Location: NESE of Sec. 32, T10S, R25E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501

180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: bgm

DATE: 07-17-2006

Legend

Existing Road
Proposed Access


TOPOGRAPHIC MAP

"B"

SHEET

8

OF 10




ENDURING RESOURCES

Southam Canyon 10-25-43-32

Southam Canyon 10-25-44-32

Pad Location: NESE of Sec. 32, T10S, R25E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: bgm

DATE: 07-17-2006

Legend

- Location
- One-Mile Radius


TOPOGRAPHIC MAP

"C"

SHEET

9

OF 10



ENDURING RESOURCES

Southam Canyon 10-25-43-32

Southam Canyon 10-25-44-32

Pad Location: NESE of Sec. 32, T10S, R25E, S.L.B.&M.



Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: bgm

DATE: 07-17-2006

Legend

- Roads
- Existing Gas Line
- Proposed Gas Line

TOPOGRAPHIC MAP

"D"

SHEET

10

OF 10



CENTER STAKE


ENDURING RESOURCES
 S.C. 10-25-43-32 & S.C. 10-25-44-32
 Pad Location:
 NESE of Sec. 32, T10S, R25E, S.L.B.&M.

Date Photographed: 11/15/2005
 Date Drawn: 07/17/2006
 Drawn By: bgm


Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

LOOKING SOUTH ACCESS





NORTH


ENDURING RESOURCES
 S.C. 10-25-43-32 & S.C. 10-25-44-32
 Pad Location:
 NESE of Sec. 32, T10S, R25E, S.L.B.&M.

Date Photographed: 11/15/2005
 Date Drawn: 07/17/2006
 Drawn By: bgm


Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

EAST





SOUTH


ENDURING RESOURCES
S.C. 10-25-43-32 & S.C. 10-25-44-32
Pad Location:
NESE of Sec. 32, T10S, R25E, S.L.B.&M.

Date Photographed: 11/15/2005
Date Drawn: 07/17/2006
Drawn By: bgm


Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

WEST



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

| | | | | | |
|---|--|---|--|--|-----------------------------|
| APPLICATION FOR PERMIT TO DRILL | | | | 5. MINERAL LEASE NO: ML-47065 | 6. SURFACE: State |
| 1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> | | | | 7. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> | | | | 8. UNIT or CA AGREEMENT NAME: | |
| 2. NAME OF OPERATOR: Enduring Resources, LLC | | | | 9. WELL NAME and NUMBER: Southam Canyon 10-25-44-32 | |
| 3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220 | | | | 10. FIELD AND POOL, OR WILDCAT: Undesignated | |
| 4. LOCATION OF WELL (FOOTAGES) 660470 X 4418582 Y 39.903932 -109.116966 AT SURFACE: 2123' FSL - 555' FEL AT PROPOSED PRODUCING ZONE: 659' FSL - 662' FEL SESE 660944 X 4418135 Y 39.899910 -109.117377 | | | | 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 10S 25E | |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 11.0 Southeast of Bonanza, UT | | | | 12. COUNTY: Uintah | 13. STATE: UTAH |
| 15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 555' | | 16. NUMBER OF ACRES IN LEASE: 640 | | 17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres | |
| 18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1000' + | | 19. PROPOSED DEPTH: 4,815 | | 20. BOND DESCRIPTION: RLB0008031 | |
| 21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5820' RT-KB | | 22. APPROXIMATE DATE WORK WILL START: 10/1/2006 | | 23. ESTIMATED DURATION: 20 days | |

24. PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | CASING SIZE, GRADE, AND WEIGHT PER FOOT | SETTING DEPTH | CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT |
|--------------|---|---------------|---|
| 20" | 14" line pipe | 40 | 3 yards Ready Mix |
| 11" | 8-5/8" J-55 24# | 1,716 | Premium Lead 110 sxs 3.50 11.1 |
| | | | Premium Tail 183 sxs 1.15 15.8 |
| 7-7/8" | 4-1/2" N-80 11.6# | 4,815 | Class G 21 sxs 3.3 11.0 |
| | | | 50/50 Poz Class G 581sxs 1.56 14.3 |
| | | | |
| | | | |
| | | | |

25. ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Alvin R. (Al) Arlian TITLE Landman - Regulatory Specialist
SIGNATURE *Al Arlian* DATE 7/19/2006

(This space for State use only)

API NUMBER ASSIGNED: 43-047-38481

APPROVAL:


RECEIVED
AUG 17 2006

DIV. OF OIL, GAS & MINING

T10S, R25E, S.L.B.&M.

ENDURING RESOURCES

WELL LOCATION, TOP OF HOLE FOR THE SOUTHAM CANYON 10-25-44-32, THE TOP OF HOLE LOCATED AS SHOWN IN THE NE 1/4 SE 1/4, THE BOTTOM HOLE LOCATED AS SHOWN IN THE SE 1/4 SE 1/4 OF SECTION 32, T10S, R25E, S.L.B.&M. UTAH COUNTY, UTAH.



WELL LOCATION:
SOUTHAM CANYON 10-25-44-32
ELEV. UNGRADED GROUND = 5804.8'

32

Top of Hole
555'


Drilling Window
2123'
200'
Bottom of Hole
659'

1975 Brass Cap
1975 Brass Cap
1975 Brass Cap
1975 Brass Cap
1975 Brass Cap
1975 Brass Cap
1975 Brass Cap
1975 Brass Cap

NOTES:

- The Bottom of hole bears S04°08'22"W 1468.37' from the Top of Hole.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. No. 189377



◆ = SECTION CORNERS LOCATED


BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (WEAVER RIDGE)

SOUTHAM CANYON 10-25-44-32
(Surface Location) NAD 83
LATITUDE = 39° 54' 14.47"
LONGITUDE = 109° 07' 03.11"


TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

| | | |
|-------------------------|-------------------|----------------------|
| DATE DRAWN: 10-27-05 | SURVEYED BY: J.H. | SHEET 2b OF 10 |
| REVISED: | DRAWN BY: F.T.M. | |
| NOTES: | SCALE: 1" = 1000' | |



8-06 Enduring Southam Cyn 00-25-44-32
Casing Schematic



| | | |
|--------------|---|-----------------------------|
| Well name: | 08-06 Enduring Southam Cyn 10-25-44-32 | |
| Operator: | Enduring Resources, LLC (N2750) | |
| String type: | Surface | Project ID: 43-047-38481 |
| Location: | Uintah County | |

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 97 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 1,874 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,059 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 1,468 ft

Directional well information:

Kick-off point 400 ft
Departure at shoe: 588 ft
Maximum dogleg: 5 °/100ft
Inclination at shoe: 38.41 °

Re subsequent strings:

Next setting depth: 4,815 ft
Next mud weight: 9.800 ppg
Next setting BHP: 2,451 psi
Fracture mud wt: 30.000 ppg
Fracture depth: 1,541 ft
Injection pressure 2,402 psi

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Internal Capacity (ft³) |
|---------|---------------------|-----------|-------------------------|-------|------------|----------------------|---------------------|---------------------|-------------------------|
| 1 | 1716 | 8.625 | 24.00 | J-55 | ST&C | 1541 | 1716 | 7.972 | 82.6 |

| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (Kips) | Tension Strength (Kips) | Tension Design Factor |
|---------|---------------------|-------------------------|------------------------|------------------|----------------------|---------------------|---------------------|-------------------------|-----------------------|
| 1 | 673 | 1370 | 2.037 | 2059 | 2950 | 1.43 | 32 | 244 | 7.55 J |

Prepared by: Helen Sadik-Macdonald
Utah Div. of Oil & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: September 5, 2006
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1541 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

08-06 Enduring Southam Cyn 10-25-44-32Operator: **Enduring Resources, LLC (N2750)**String type: **Production**

Project ID:

43-047-38481Location: **Uintah County****Design parameters:****Collapse**Mud weight: 9.800 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 142 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 1,380 ft

BurstMax anticipated surface
pressure: 1,874 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,451 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)**Directional well information:**Kick-off point 400 ft
Departure at shoe: 1468 ft
Maximum dogleg: 5 °/100ft
Inclination at shoe: 0 °

Tension is based on buoyed weight.

Neutral point: 4,554 ft

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Internal Capacity (ft³) |
|------------|---------------------------|-------------------------------|-------------------------------|------------------------|----------------------------|----------------------------|---------------------------|-------------------------------|-------------------------------|
| 1 | 5259 | 4.5 | 11.60 | N-80 | LT&C | 4815 | 5259 | 3.875 | 121.9 |
| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (Kips) | Tension Strength (Kips) | Tension Design Factor |
| 1 | 2451 | 6350 | 2.590 | 2451 | 7780 | 3.17 | 48 | 223 | 4.68 J |

Prepared Helen Sadik-Macdonald
by: Utah Div. of Oil & MiningPhone: 801-538-5357
FAX: 801-359-3940Date: September 5, 2006
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 4815 ft, a mud weight of 9.8 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

From: Robert Clark
To: Whitney, Diana
Date: 8/28/2006 2:49:59 PM
Subject: RDCC short turn around responses

43-047-384 P3

The following comments are provided in response to short turn around items **RDCC #6950** through **RDCC #6952**, and **RDCC #6988** through **RDCC # 6990**.

RDCC #6950, Comments begin: The Houston Exploration Company's proposal to drill the **Squaw Ridge 14-16-7-25** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm. The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm. **Comments end.**

RDCC # 6951, Comments begin: The Enduring Resources, LLC proposal to drill the **Southam Canyon 10-25-44-32** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm. The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm. **Comments End.**

RDCC #6952, Comments begin: The Enduring Resources, LLC proposal to drill the **Buck Camp 12-22-14-2** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm. The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm. **Comments end. RDCC**

#6988, Comments begin: The Houston Exploration Company's proposal to drill the **Gusher 13-11-5-19** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm. The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an

area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm . **Comments end. RDCC # 6989, Comments begin:** The Enduring Resources, LLC proposal to drill the **Buck Camp 12-22-23-2** wildcat well, in Uintah County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm . The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm **Comments end. RDCC # 6990, Comments begin:** The RBDR, LLC proposal to drill the **Crazy "R" Ranch #1** wildcat well, in Sevier County, may require a permit, known as an Approval Order, from the Executive Secretary of the Air Quality Board. If any compressor or pump stations are constructed at the site, a permit application, known as a Notice of Intent (NOI), should be submitted to the Executive Secretary at the Utah Division of Air Quality at 150 N. 1950 West, Salt Lake City, Utah, 84116 for review according to the Utah Air Quality Rule R307-401. Permit: Notice of Intent and Approval Order. A copy of the rules is found at www.rules.utah.gov/publicat/code/r307/r307.htm . The proposed project, in Uintah County, is also subject to Utah Air Quality Rule R307-205-5, Fugitive Dust, due to the fugitive dust that is generated during the excavating phases of the project. These rules apply to construction activities that disturb an area greater than 1/4 acre in size. A permit, known as an Approval Order, is not required from the Executive Secretary of the Air Quality Board, but steps need to be taken to minimize fugitive dust, such as watering and/or chemical stabilization, providing vegetative or synthetic cover or windbreaks. A copy of the rules may be found at www.rules.utah.gov/publicat/code/r307/r307.htm **Comments end.** Robert Clark Division of Air Quality 536-4435

CC: McNeill, Dave; Wright, Carolyn

MEMORANDUM

DATE: August 29, 2006

TO: Utah Division of Oil, Gas and Mining, and Resource Development
Coordinating Committee

FROM: Utah Geological Survey, Ground Water and Paleontology Program

SUBJECT: UGS comments on RDCC items 6950, 6951, 6952, 6958, 6959, 6989,
6996, 6997, 6998, and 6999

6950. Trust Lands Administration, State Lease # ML-47954-A
Sec. 16, T7S, R25E, Uintah County

There are a number paleontological localities recorded in our files in this project area and it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6951. Trust Lands Administration, State Lease # ML-47965
Sec. 32, T10S, R25E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6952. Trust Lands Administration, State Lease # ML-47987
Sec. 2, T12S, R22E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6958. Trust Lands Administration, Seismic and Vibro Surveys, Sec. 2 & 36, T21S, R18E; Sec. 16, 33, 34, & 35, T21S, R19E; Sec. 2, T22S, R18E; and Sec. 2, 3, 4, 9, 10, 11, 14, 15, 16, 21, 22, 23, & 24, T21S, R18E; Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6959. Trust Lands Administration, SULA #1470, Sec. 36, T29S, R20E; Sec. 36, T29.5S, R20E; and Sec. 32, T30S, R20E; San Juan County

Although there are no paleontological localities recorded in our files in this project area, significant vertebrate fossil localities have been reported nearby in the Permian strata. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit by a paleontologist with a valid state permit.

6989. Trust Lands Administration, State Lease # ML-47087
Sec. 2, T12S, R22E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6996. Division of Oil, Gas and Mining, Short Turn Around, Application for Permit to Drill - proposal to drill a wildcat well the Knight 14-30 on a Fee lease
Sec. 30, T3S, R2E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6997. Division of Oil, Gas and Mining, Short Turn Around, Application for Permit to

Drill - proposal to drill the Deep Creek 2-30 on a Fee lease, Sec. 30, T3S, R2E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6998. Division of Oil, Gas and Mining, Short Turn Around, Application for Permit to Drill - proposal to drill a wildcat well the Knight 16-30 on a Fee lease, Sec. 30, T3S, R2E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

6999. Division of Oil, Gas and Mining, Short Turn Around, Application for Permit to Drill - proposal to drill a wildcat well the Eliason 6-30 on a Fee lease, Sec. 30, T3S, R2E, Uintah County

Although there are no paleontological localities recorded in our files in this project area, it is mapped as T3 (Eocene Uinta and Duchesne River Formations) on the Utah State Geological Map. The Uinta and Duchesne River Formations are among the most paleontological sensitive rock units in Utah and have a strong potential for yielding significant vertebrate fossil localities. The office of the State paleontologist therefore recommends that a paleontological survey be conducted for this project and its easements by a paleontologist with a valid state permit.

API NO. ASSIGNED: 43-047-38481

PHONE NUMBER: 303-350-5114

INSPECT LOCATN BY: / /

FIELD NAME: WILDCAT (1)

COALBED METHANE WELL? NO

LOCATION AND SITING:

_____ R649-2-3.
 Unit: _____
 _____ R649-3-2. General
 Siting: 460 From Qtr/Qtr & 920' Between Wells
 _____ R649-3-3. Exception
 _____ Drilling Unit
 Board Cause No: _____
 Eff Date: _____
 Siting: _____
 ✓ R649-3-11. Directional Drill


COMMENTS :

STIPULATIONS:

Needs Profile (03-07-06)

- 1- Spacing Strip
- 2- STATEMENT OF BASIS
- 3- Surf - C_s Cont Strip

T10S R25E



T11S R25E

OPERATOR: ENDURING RES LLC (N2750)

SEC: 32 T.10S R. 25E

FIELD: WILDCAT (001)

COUNTY: UTAH

SPACING: R649-3-11 / DIRECTIONAL DRILLING

Field Status
 ABANDONED
 ACTIVE
 COMBINED
 INACTIVE
 PROPOSED
 STORAGE
 TERMINATED

Unit Status
 EXPLORATORY
 GAS STORAGE
 NF PP OIL
 NF SECONDARY
 PENDING
 PI OIL
 PP GAS
 PP GEOTHERML
 PP OIL
 SECONDARY
 TERMINATED

Wells Status
 GAS INJECTION
 GAS STORAGE
 LOCATION ABANDONED
 NEW LOCATION
 PLUGGED & ABANDONED
 PRODUCING GAS
 PRODUCING OIL
 SHUT-IN GAS
 SHUT-IN OIL
 TEMP. ABANDONED
 TEST WELL
 WATER INJECTION
 WATER SUPPLY
 WATER DISPOSAL
 DRILLING



PREPARED BY: DIANA WHITNEY
 DATE: 18-AUGUST-2006

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: _____ ENDURING RESOURCES, LLC.

WELL NAME & NUMBER: _____ SOUTHAM CANYON 10-25-44-32

API NUMBER: _____ 43-047-38481

LOCATION: 1/4,1/4 NESE Sec: 32 TWP: 10S RNG: 25E 2123' FSL 555' FEL

Geology/Ground Water:

Enduring proposes to set 2,000' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 5,800' which is below the proposed T.D. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 32. The surface formation at this site is the Uinta-Green River Formation transition. The Uinta Formation is made up of lenticular sandstones interbedded with shales and is expected to have limited value as an aquifer. The Green river Formation should be found near the surface. The Green River Formation may contain useable aquifers but they should be adequately protected by the proposed casing and cementing program.

Reviewer: _____ Brad Hill Date: _____ 08-28-06

Surface:

The pre-drill investigation of the surface was performed on 03/07/2006. This site is on state surface, with state minerals. Due to harsh weather, Jim Davis from SITLA was not present but expressed that the pre-sites should still take place in his absence. Doug Hammond expressed willingness and desire to paint the location tanks in a color to closely match the surroundings. Ben Williams of DWR stated that this section is classified as critical deer and substantial elk winter range. Because of the critical deer classification, Mr. Williams requested that the location be closed to drilling and construction from November 15 to April 15.

Reviewer: _____ Richard Powell Date: _____ 03/07/2006

Conditions of Approval/Application for Permit to Drill:

1. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: ENDURING RESOURCES, LLC
WELL NAME & NUMBER: SOUTHAM CANYON 10-25-44-32
API NUMBER: 43-047-38481
LEASE: ML-47065 **FIELD/UNIT:** UNDESIGNATED
LOCATION: 1/4, 1/4 NESE **Sec:** 32 **TWP:** 10S **RNG:** 25E 2123' **FSL** 555' **FEL**
LEGAL WELL SITING: 460 **F SEC. LINE;** 460 **F 1/4, 1/4 LINE;** 920 **F ANOTHER WELL.**
GPS COORD (UTM): 4418594Y 0660980X **SURFACE OWNER:** SITLA.

PARTICIPANTS

Richard Powell (DOGM), Doug Hammond (Enduring Resources), Larry Rowell (Ponderosa Oilfield Service), Chris Stewart & Dustin Laub (TriState Land Surveying).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Area of location slopes gently south inside a small valley with hills directly to the east and west of proposed location. A small wash hugs the west side of the valley. Hills and ridges dominate the terrain of this section, with rock formations protruding from the tops of many of the slopes. The slopes of the western half of this section are much more gradual. The ridges generally seem to run from north to south. Drainage is westward to Evacuation Creek. To the east of this section, are much taller and steeper slopes. Bonanza, UT is approximately 11 miles to the north.

SURFACE USE PLAN

CURRENT SURFACE USE: Wildlife & Livestock grazing.

PROPOSED SURFACE DISTURBANCE: Location will be 375' by 250'. Proposed new access road to be approximately 3430'. The last 1900' of the new access will be for this well only, several other wells are proposed to be accessed from the first 1530' feet.

LOCATION OF EXISTING WELLS WITHIN A 1-MILE RADIUS: See attached map from GIS database.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production facilities will be on location and added after drilling well. Pipeline to follow access road.

SOURCE OF CONSTRUCTION MATERIAL: All construction material will be borrowed from site during construction of location.

ANCILLARY FACILITIES: None will be required.

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST OF CONCERNS? (EXPLAIN): Unlikely.

WASTE MANAGEMENT PLAN:

Drilled cuttings will be settled into reserve pit. Liquids from pit will be allowed to evaporate. Formation water will be confined to storage tanks. Portable toilets, sewage holding tanks, and onsite sewage treatment equipment will be handled by commercial contractors and regulated by the appropriate health authority. Trash will be contained in trash baskets and disposed of at an approved landfill.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: none

FLORA/FAUNA: Sagebrush, Greasewood, spiny hopsage, shadscale / Deer, elk, Rodents, Coyote, Songbirds, Rabbit, Bobcat, Pronghorn, Cougar.

SOIL TYPE AND CHARACTERISTICS: Light brown silty clay with scattered rock and shale.

EROSION/SEDIMENTATION/STABILITY: Very little natural erosion. Sedimentation and stability are not a problem and location construction shouldn't cause an increase in stability or erosion problems.

PALEONTOLOGICAL POTENTIAL: Paleontology study by IPC on 3/1/06.

RESERVE PIT

CHARACTERISTICS: 215' BY 75' and twelve feet deep.

LINER REQUIREMENTS (Site Ranking Form attached): A liner will be required for reserve pit. Site ranking score is 25.

SURFACE RESTORATION/RECLAMATION PLAN

As per SITLA.

SURFACE AGREEMENT: As per SITLA.

CULTURAL RESOURCES/ARCHAEOLOGY: Archaeology study done by MOAC 2/23/06.

OTHER OBSERVATIONS/COMMENTS

This directional well shares a pad with the Southam Canyon 10-25-43-32.

ATTACHMENTS

Photos of this site were taken and placed on file.

RICHARD POWELL
DOGM REPRESENTATIVE

03/07/06 10:35 AM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**


| <u>Site-Specific Factors</u> | <u>Ranking</u> | <u>Site Ranking</u> |
|---|----------------|---------------------|
| Distance to Groundwater (feet) | | |
| >200 | 0 | |
| 100 to 200 | 5 | |
| 75 to 100 | 10 | |
| 25 to 75 | 15 | |
| <25 or recharge area | 20 | <u>0</u> |
| Distance to Surf. Water (feet) | | |
| >1000 | 0 | |
| 300 to 1000 | 2 | |
| 200 to 300 | 10 | |
| 100 to 200 | 15 | |
| < 100 | 20 | <u>0</u> |
| Distance to Nearest Municipal Well (feet) | | |
| >5280 | 0 | |
| 1320 to 5280 | 5 | |
| 500 to 1320 | 10 | |
| <500 | 20 | <u>0</u> |
| Distance to Other Wells (feet) | | |
| >1320 | 0 | |
| 300 to 1320 | 10 | |
| <300 | 20 | <u>0</u> |
| Native Soil Type | | |
| Low permeability | 0 | |
| Mod. permeability | 10 | |
| High permeability | 20 | <u>20</u> |
| Fluid Type | | |
| Air/mist | 0 | |
| Fresh Water | 5 | |
| TDS >5000 and <10000 | 10 | |
| TDS >10000 or Oil Base Mud Fluid | 15 | |
| containing significant levels of hazardous constituents | 20 | <u>5</u> |
| Drill Cuttings | | |
| Normal Rock | 0 | |
| Salt or detrimental | 10 | <u>0</u> |
| Annual Precipitation (inches) | | |
| <10 | 0 | |
| 10 to 20 | 5 | |
| >20 | 10 | <u>0</u> |
| Affected Populations | | |
| <10 | 0 | |
| 10 to 30 | 6 | |
| 30 to 50 | 8 | |
| >50 | 10 | <u>0</u> |
| Presence of Nearby Utility Conduits | | |
| Not Present | 0 | |
| Unknown | 10 | |
| Present | 15 | <u>0</u> |


Final Score 25 (Level I Sensitivity)

Sensitivity Level I = 20 or more: total containment is required.


Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.





STATE ACTIONS
Resource Development Coordinating Committee
Governor's Office of Planning and Budget
5110 State Office Building
SLC, UT 84114
Phone No. 537-9230

| | |
|---|--|
| 1. State Agency Oil, Gas and Mining 1594 West North Temple, Suite 1210 Salt Lake City, UT 84114-5801 | 2. Approximate date project will start: Upon Approval or September 1, 2006 |
| 3. Title of proposed action: Application for Permit to Drill | |
| 4. Description of Project: Enduring Resources, LLC proposes to drill the Southam Canyon 10-25-44-32 well (wildcat) on State lease ML-47065, Uintah County, Utah. This action is being presented to the RDCC for consideration of resource issues affecting state interests. The Division of Oil, Gas and Mining is the primary administrative agency in this action and must issue approval before operations commence. | |
| 5. Location and detailed map of land affected (site location map required, electronic GIS map preferred) (include UTM coordinates where possible) (indicate county) 2123' FSL 555' FEL, NE/4 SE/4, Section 32, Township 10 South, Range 25 East, Uintah County, Utah | |
| 6. Possible significant impacts likely to occur: Surface impacts include up to five acres of surface disturbance during the drilling and completion phase (estimated for five weeks duration). If oil and gas in commercial quantities is discovered, the location will be reclaimed back to a net disturbance of between one and two acres – not including road, pipeline, or utility infrastructure. If no oil or gas is discovered, the location will be completely reclaimed. | |
| 7. Identify local government affected a. Has the government been contacted? No. b. When? c. What was the response? d. If no response, how is the local government(s) likely to be impacted? | |
| 8. For acquisitions of land or interests in land by DWR or State Parks please identify state representative and state senator for the project area. Name and phone number of state representative, state senator near project site, if applicable: a. Has the representative and senator been contacted? N/A | |
| 9. Areawide clearinghouse(s) receiving state action: (to be sent out by agency in block 1) Uintah Basin Association of Governments | |
| 10. For further information, contact: Diana Whitney Phone: (801) 538-5312 | 11. Signature and title of authorized officer  Gil Hunt, Associate Director Date: August 18, 2006 |

475 17th Street, Suite 1500
Denver, CO 80202
(303) 573-1222
(303) 573-0461

Enduring Resources

Fax

| | | | |
|---|----------------------------|---------------|----------------|
| To: | Helen Sadik-Macdonald | From: | Evette Bissett |
| Fax: | 801-359-3940 | Pages: | 7 |
| Phone: | | Date: | 8/30/2006 |
| Re: | Southam Canyon 10-25-44-32 | cc: | |
| <input type="checkbox"/> Urgent <input checked="" type="checkbox"/> For Review <input type="checkbox"/> Please Comment | | | |
| <input type="checkbox"/> Please Reply <input type="checkbox"/> Please Recycle | | | |

● **Comments**

Corrected cover page and drilling plan

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

 AMENDED REPORT ☐
(highlight changes)

| APPLICATION FOR PERMIT TO DRILL | | | | 5. MINERAL LEASE NO: ML-47065 | 6. SURFACE: State |
|--|--|--|--|---|----------------------|
| 1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> | | | | 7. IF INDIAN, ALLOTTEE OR TRIBE NAME: | |
| B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> | | | | 8. UNIT or CA AGREEMENT NAME: | |
| 2. NAME OF OPERATOR: Enduring Resources, LLC | | | | 9. WELL NAME and NUMBER: Southam Canyon 10-25-44-32 | |
| 3. ADDRESS OF OPERATOR: 475 17th St., Ste 1500 CITY Denver STATE CO ZIP 80220 | | | | 10. FIELD AND POOL, OR WILDCAT: Undesignated | |
| 4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2123' FSL - 555' FEL AT PROPOSED PRODUCING ZONE: 659' FSL - 662' FEL SESE | | | | 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 10S 25E | |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 11.0 Southeast of Bonanza, UT | | | | 12. COUNTY: Utah | 13. STATE: UTAH |
| 15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 555' | | 18. NUMBER OF ACRES IN LEASE: 640 | | 17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 acres | |
| 18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1000' + | | 19. PROPOSED DEPTH: 5,259 | | 20. BOND DESCRIPTION: RLB0008031 | |
| 21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5820' RT-KB | | 22. APPROXIMATE DATE WORK WILL START: 10/1/2006 | | 23. ESTIMATED DURATION: 20 days | |

| 24. PROPOSED CASING AND CEMENTING PROGRAM | | | | | | | |
|---|---|-----------|-------|---------------|---|-----------|-----------|
| SIZE OF HOLE | CASING SIZE, GRADE, AND WEIGHT PER FOOT | | | SETTING DEPTH | CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT | | |
| 20" | 14" | line pipe | | 40 | 3 yards | Ready Mix | |
| 11" | 8-5/8" | J-55 | 24# | 1,716 | Premium Lead | 110 sxs | 3.50 11.1 |
| | | | | | Premium Tail | 183 sxs | 1.15 15.8 |
| 7-7/8" | 4-1/2" | N-80 | 11.6# | 5,259 | Class G | 21 sxs | 3.3 11.0 |
| | | | | | 50/50 Poz Class G | 662sxs | 1.56 14.3 |
| | | | | | | | |
| | | | | | | | |

| 25. ATTACHMENTS | |
|---|--|
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES: | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) Alvin R. (Al) Arlian TITLE Landman - Regulatory Specialist

SIGNATURE *Al Arlian* DATE 7/19/2006

(This space for State use only)

API NUMBER ASSIGNED: _____

APPROVAL: _____

(11/2001)

(See Instructions on Reverse Side)

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

**Enduring Resources, LLC
Southam Canyon 10-25-44-32
SE-SE 32-10S-25E (Bottom Hole Location)
NE-SE 32-10S-25E (Surface Location)
Uintah County, Utah
State Lease: ML-47065**

ONSHORE ORDER 1 - DRILLING PLAN

1. Estimated Tops of Geological Markers:

| Formation | Depth (K.B.) |
|-------------|--------------|
| Uinta | Surface |
| Green River | Surface |
| Wasatch | 2030 |
| Mesaverde | 2890 |

2. Estimated Depths of Anticipated Water, Oil, Gas or Other Minerals:

| Substance | Formation | Depth (K.B.) |
|-----------|--------------------------|--------------|
| | KB-Uinta Elevation: 5820 | |
| Oil / Gas | Green River | Surface |
| Oil / Gas | Wasatch | 2030 |
| Oil / Gas | Mesaverde | 2890 |
| | Estimated TD | 5259 |

An 11" hole will be drilled to only approximately 1,716 feet because it is a directional well. The depth will be determined by the depth that the Birds Nest zone is encountered. The hole will be drilled 400 feet beyond the top of the Birds Nest zone and surface casing will be set.

3. Pressure Control Equipment: (3000 psi schematic attached)

- A. Type: Eleven (11) inch double gate hydraulic BOP with eleven (11) inch annular preventer on 3,000 psi casinghead, with 3,000 psi choke manifold equipped per the attached diagram. BOPE as specified in *Onshore Oil & Gas Order Number 2*. A PVT, stroke counter and flow sensor will be installed to check for flow and monitor pit volume.
- B. Pressure Rating: 3,000 psi BOPE
- C. Kelly will be equipped with upper and lower Kelly valves.
- D. Testing Procedure: Annular Preventer

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

Enduring Resources, LLC Southam Canyon 10-25-44-32 Page - 2 -

At a minimum, the annular preventer will be pressure tested to 50% of the stack rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the annular preventer is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

1. When the BOP is initially installed;
2. Whenever any seal subject to test pressure is broken;
3. Following related repairs; and
4. At thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day. All BOP drills and tests will be recorded in the IADC driller's log.

E. Miscellaneous Information:

The blowout preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

4. Proposed Casing & Cementing Program:**A. Casing Program: All New**

| Hole Size | Casing Size | Wt./Ft. | Grade | Joint | Depth Set (MD) |
|-----------|-------------|---------|-------|-------|----------------------|
| 20" | 14" O.D. | | | | 40' (GL) |
| 11" | 8-5/8" | 24# | J-55 | ST&C | 0 - 1,716' (KB) est. |
| 7-7/8" | 4-1/2" | 11.6# | N-80 | LT&C | 0 - 5259' (KB) |

The surface casing will have guide shoe, 1 joint, insert float collar. Centralize the shoe joint with bowspring centralizers in the middle and top of the joint and the next 16 joints

RECEIVED**AUG 30 2006**

Enduring Resources, LLC Southam Canyon 10-25-44-32 Page - 3 -
 with bowspring centralizers on every other collar (8 centralizers total). Thread lock guide shoe.

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

B. Casing Design Parameters:

| Depth (MD) | Casing | Collapse(psi)/SF | Burst (psi)/SF | Tension(mlbs)/SF |
|------------|-----------------------------|------------------|----------------|------------------|
| 40' (GL) | 14" OD | | | |
| 1716' (KB) | 8-5/8", 24#/ft, J55, STC | 1370/1.52(a) | 2950/3.28(b) | 244/5.81(c) |
| 5259' (KB) | 4-1/2", 11.6#/ft, N-80, LTC | 6350/2.32(d) | 7780/3.10(e) | 223/4.25(f) |

- (a.) based on full evacuation of pipe with 8.6 ppg fluid on annulus
- (b.) based on 8.6 ppg gradient with no fluid on annulus
- (c.) based on casing string weight in 8.6 ppg mud
- (d.) based on full evacuation of pipe with 10.0 ppg fluid on annulus
- (e.) based on 9.2 ppg gradient, gas to surface, with no fluid on annulus, no gas gradient
- (f.) based on casing string weight in 9.2 ppg mud

PROPOSED CEMENTING PROGRAM

Surface Casing (if well will circulate)-Cemented to surface

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|--------|-------------|---|-----|------------|--------------|-----------------------------|
| 8-5/8" | Lead | 1216 | Premium cement + 16% gel + 0.25 pps celloflake | 110 | 25% | 11.1 | 3.50 |
| 8-5/8" | Tail | 500 | Premium cement + 2% CaCl ₂ + 0.25 pps celloflake | 138 | 25% | 15.8 | 1.15 |

A cement top job is required if cement fallback is greater than 10' below ground level. Top job (weight 15.8 ppg, yield 1.15 ft³/sx) cement will be premium cement w/ 3% CaCl₂ + 0.25 pps celloflake. Volume as required

Surface Casing (if well will not circulate) - Cemented to surface

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|---------|-------------|---|---------|------------|--------------|-----------------------------|
| 8-5/8" | Lead | 500 | Premium cement + 2% CaCl ₂ + 0.25 pps celloflake | 138 | 25 | 15.8 | 1.15 |
| 8-5/8" | Top job | As req. | Premium cement + 3% CaCl ₂ + 0.25 pps celloflake | As Req. | | 15.8 | 1.15 |

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

Production Casing and Liner - Cemented TD to 300' above base of surface casing

| CASING | SLURRY | FT. of FILL | CEMENT TYPE | SXS | EXCESS (%) | WEIGHT (ppg) | YIELD (ft ³ /sx) |
|--------|--------|-------------------|---|-----|---------------|-----------------|--------------------------------|
| 4-1/2" | Lead | 214 | Class "G" + 5% NaCl + 12% Gel + 0.25 pps celloflake + 0.2% antifoam + 0.25% fluid loss + 1% extender | 24 | 25 | 11.0 | 3.3 |
| 4-1/2" | Tail | 3629 | 50/50 POZ Class G + 2% gel +1% CaCl ₂ + 0.2% dispersant + 0.2% fluid loss + 0.1% antifoam | 662 | 25 | 14.3 | 1.56 |

Cement volumes for the 4-1/2" Production Casing will be calculated to provide a top of cement to 300' above base of surface casing. Cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole. Actual cement types may vary due to hole conditions and cement contractor used.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. **Drilling Fluids (mud) Program:**

| Interval (MD) | Mud Weight | Fluid Loss | Viscosity | Mud Type |
|-------------------|------------|------------|-----------|-----------|
| 0' - 1716' (KB) | | No cntrl | | Air/mist |
| 1,716'-3000' (KB) | 8.4-8.6 | No cntrl | 28-36 | Water |
| 3000'-5259' (KB) | 8.8-9.8 | 8 - 10 ml | 32-42 | Water/Gel |

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

6. **Evaluation Program:**

Tests: No tests are currently planned.

Coring: No cores are currently planned.

Samples: No sampling is currently planned.

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

Logging

- Dual Induction – SFL /Gamma Ray/Caliper/SP/TDLT/CNL/ML
TD to Base Surface Casing
- Cement Bond Log / Gamma Ray:
TD to Base of Surface Casing or Top of Cement if below Base of Surface Casing

Stimulation: A stimulation or frac treatment will be designed for completion of this well based on openhole log analysis. The drill site, as approved, will be sufficient size to accommodate all completion activities.

7. Abnormal Conditions:

No abnormal temperatures or pressures are anticipated. No H₂S has been encountered or known to exist from previous wells drilled to similar depths in the general area.

Maximum anticipated bottom hole pressure equals approximately 2735 psi (calculated at 0.52psi/foot of hole) and maximum anticipated surface pressure equals approximately 1578 psi (anticipated bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. Anticipated Starting Dates:

- Anticipated Commencement Date- Within one year of APD issue.
- Drilling Days- Approximately 10 days
- Completion Days - Approximately 10 days
- Anticipate location construction within 30 days of permit issue.

9. Variances:

None anticipated

10. Other:

A Cultural Resource Inventory and Paleontology reconnaissance shall be conducted for the well location, access route and pipeline. The reports shall be submitted to the Division of Oil, Gas and Mining and the School and Institutional Trust lands Administration upon their receipt.

Single Shot directional surveys will be dropped every 2000 feet to monitor hole angle.

RECEIVED

AUG 30 2006

DIV. OF OIL, GAS & MINING

From: Ed Bonner
To: Mason, Diana
Date: 12/18/2006 1:42 PM
Subject: Well Clearance

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

Dominion E&P, Inc
LCU 16-2H (API 43 047 38675)

Enduring Resources, LLC
Southam Canyon 10-25-44-32 (API 43 047 38481)

Kerr McGee Oil & Gas Onshore LP
Bonanza 1023-2D-4 (API 43 047 38761)
Bonanza 1023-2O-1 (API 43 047 38762)
State 1022-25O (API 43 047 38851)

If you have any questions regarding this matter please give me a call.



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

December 18, 2006

Enduring Resources, LLC
475 17th St., Ste. 1500
Denver, CO 80202


Re: Southam Canyon 10-25-44-32 Well, 2123' FSL, 555' FEL, NE SE, Sec. 32,
T. 10 South, R. 25 East, Bottom Location 659' FSL, 662' FEL, SE SE, Sec. 32,
T. 10 South, R. 25 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-38481.

Sincerely,


for Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor (via e-mail)
SITLA

Operator: Enduring Resources, LLC
Well Name & Number Southam Canyon 10-25-44-32
API Number: 43-047-38481
Lease: ML-47065

Location: NE SE **Sec.** 32 **T.** 10 South **R.** 25 East
Bottom Location: SE SE **Sec.** 32 **T.** 10 South **R.** 25 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

5. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

6. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

7. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
8. Surface casing shall be cemented to the surface.
9. Operator shall comply with applicable recommendations resulting from Resource Development Coordinating Committee review. Statements attached.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|---|--|--|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47065 |
| 2. NAME OF OPERATOR: Enduring Resources, LLC | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a |
| 3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202 | | 7. UNIT or CA AGREEMENT NAME: n/a |
| PHONE NUMBER: (303) 350-5719 | | 8. WELL NAME and NUMBER: Southam Canyon 10-25-44-32 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2123' FSL - 555' FEL | | 9. API NUMBER: 4304738481 |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 10S 25E S | | 10. FIELD AND POOL, OR WILDCAT: Undesignated |
| COUNTY: Uintah | | STATE: UTAH |

| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | |
|--|---|---|--|
| TYPE OF SUBMISSION | TYPE OF ACTION | | |
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: Request for APD Extension |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 12/18/2007
TO: 12/18/2008

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12-18-07
By: [Signature]

COPY SENT TO OPERATOR
Date: 12-18-2007
Initials: KS

| | |
|--|---------------------------------------|
| NAME (PLEASE PRINT) Alvin R. (Al) Arlian | TITLE Landman - Regulatory Specialist |
| SIGNATURE [Signature] | DATE 12/14/2007 |

(This space for State use only)

RECEIVED
DEC 17 2007
DIV. OF OIL, GAS & MINING



**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738481
Well Name: Southam Canyon 10-25-44-32
Location: 2123' FSL - 555' FEL, NESE, Sec 32, T10S-R25E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 12/18/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

12/14/2007

Date

Title: Landman - Regulatory Specialist

Representing: Enduring Resources, LLC

RECEIVED
DEC 17 2007
OFFICE OF THE ATTORNEY GENERAL

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

CONFIDENTIAL

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|---|--|--|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-47065 |
| 2. NAME OF OPERATOR: Enduring Resources, LLC | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a |
| 3. ADDRESS OF OPERATOR: 475 17th Street, Suite 1500 CITY Denver STATE CO ZIP 80202 | | 7. UNIT or CA AGREEMENT NAME: n/a |
| PHONE NUMBER: (303) 350-5114 | | 8. WELL NAME and NUMBER: Southam Canyon 10-25-44-32 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 2123' FSL - 555' FEL | | 9. API NUMBER: 4304738481 |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NESE 32 10S 25E S | | 10. FIELD AND POOL, OR WILDCAT: Undesignated |
| COUNTY: Uintah | | STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|--|
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: Request for APD Extension |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Enduring Resources, LLC respectfully request an extension to the expiration date of this Application for Permit to Drill

FROM: 12/18/2008
TO: 12/18/2009

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12-22-08
By: 

| | |
|---|---------------------------------------|
| NAME (PLEASE PRINT) Alvin R. (Al) Arlian | TITLE Landman - Regulatory Specialist |
| SIGNATURE  | DATE 12/8/2008 |

(This space for State use only)

COPY SENT TO OPERATOR

Date: 12-30-2008

Initials: KS

(5/2000)

(See Instructions on Reverse Side)

RECEIVED

DEC 18 2008

DIV. OF OIL, GAS & MINING



**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4304738481
Well Name: Southam Canyon 10-25-44-32
Location: 2123' FSL - 555' FEL, NESE, Sec 32, T10S-R25E
Company Permit Issued to: Enduring Resources, LLC
Date Original Permit Issued: 12/18/2006

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

12/8/2008
Date

Title: Administrative Assistant

Representing: Enduring Resources, LLC

RECEIVED
DEC 18 2008
DIV. OF OIL, GAS & MINING



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

January 7, 2010

Al Arlian
Enduring Resources, LLC
475 17TH Street Ste 1500
Denver, CO 80202


Re: APD Rescinded – Southam Cyn 10-25-44-32, Sec. 32 T.10S, R. 25E
Uintah County, Utah API No. 43-047-38481

Dear Mr. Arlian:

The Application for Permit to Drill (APD) for the subject well was approved by the Division of Oil, Gas and Mining (Division) on December 18, 2006. On December 18, 2007 and December 22, 2008 the Division granted a one-year APD extension. No drilling activity at this location has been reported to the division. Therefore, approval to drill the well is hereby rescinded, effective January 7, 2010.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
SITLA, Ed Bonner